
## TYPICAL APPLICATION OF TRAFFIC CONTROL **DEVICES FOR ROAD CLOSURE**



TT TYPE III BARRICADE (SEE NOTE 1)

FLASHING AMBER LIGHT

## GENERAL NOTES

- 1. TYPE III BARRICADES SHALL BE AS SHOWN ON STANDARD 702001 "TYPICAL APPLICATIONS OF TYPE III BARRICADES CLOSING A ROAD". EACH TYPE III BARRICADE SHALL HAVE TWO FLASHING AMBER LIGHTS MOUNTED ABOVE IT.
- 2. IF THE ROAD IS OPEN TO LOCAL TRAFFIC OR "D" EXCEEDS 1000' (300 m), ANOTHER SET OF TYPE III BARRICADES, EQUIPPED AS IN NOTE 1 ABOVE, SHALL BE PLACED AT EACH END OF THE WORK AREA.
- 3. WHEN A STOP CONDITION EXISTS, AS SHOWN ABOVE, NO SIGNS ARE REQUIRED IN ADVANCE OF THE "STOP" SIGN WHEN THE ROAD IS CLOSED WITHIN 100' (30 m) OF THE INTERSECTION.
- 4. STANDARD 702001 SHALL APPLY FOR THE PLACEMENT & DESIGN OF TYPE III BARRICADES.

- 5. ALL SIGNS SHALL BE POST MOUNTED IF THE CLOSURE TIME EXCEEDS FOUR DAYS.
- 6. A MINIMUM OF TWO FLASHING LIGHTS SHALL BE USED AT NIGHT ON EACH APPROACH IN ADVANCE OF THE WORK AREA. FLASHING LIGHTS SHALL BE INSTALLED ABOVE THE FIRST TWO SIGNS IN THE SERIES.
- 7. LONGITUDINAL DIMENSIONS MAY BE ADJUSTED SLIGHTLY TO FIT FIELD CONDITIONS.
- 8. FORMS BT. 725 AND BT. 726 ARE REQUIRED.
- 9. WHEN A SIDEROAD INTERSECTS THE HIGHWAY ON WHICH WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC DEVICES SHALL BE ERECTED AND PROVIDED AS DIRECTED BY THE ENGINEER.

F.A.I. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.				
72		MACON	135	117				
* (58-62,58-62-1,58-63)RS								


## DETAIL OF CONCRETE MEDIAN, TYPE SM (SPECIAL)

GENERAL NOTES

- 1. THE GENERAL NOTES FOR STANDARD 606301 SHALL APPLY.
- 2. SECTION G-G SHALL BE THE SAME AS SHOWN ON STANDARD 606301. 3. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE FOOT (m<sup>2</sup>) FOR CONCRETE MEDIAN, TYPE SM (SPECIAL), INCLUDING THE COST OF FURNISHING AND INSTALLING THE DOWEL


BARS, MORTAR FILLING, PAVEMENT FABRIC AND THE REMOVAL AND

4. OPENINGS FOR SIGNS IN MEDIANS AND ISLANDS SHALL BE AS SHOWN OR AS DIRECTED BY THE ENGINEER.



WIDTH AS SHOWN IN THE PLANS PAYEMENT FABRIC 63\*/100 SQ FT (3.07 kg/m<sup>2</sup>)/ STANDARD 420701 SLOPE TO DRAIN (100) PROPOSED BITUMINOUS
RESURFACING DISPOSAL OF THE EXISTING PAVEMENT FOR THE 14"  $\times$  14" (350  $\times$  350) OPENING, IF REQUIRED, AND NO ADDITIONAL COMPENSATION WILL

MORTAR FILLING AROUND
DOWEL BARS (TYP.) (350) CONSTRUCT 14" × 14" (350 × 350) OPENING #4 (#10) DEFORMED TIE BARS @ 36" (900) SECTION A-A



## PLAN OF MEDIAN

	NAME	DATE	REVISIONS			
DESIGNED	J.M.H.	1-89	NAME	DATE	ALL DIMENSIONS ARE IN	
CHECKED	F.M.S.	1-89	J.Y.B.	06/02	INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.	
CADD NO.	A-5	.08	K.A.G.	06/03	UNLESS OTHERWISE SHOWN.	

PLAN OF CORNER ISLAND

NAME DATE REVISIONS DESIGNED J.H.M. 8-11-87 NAME DATE P.E.K. 8-25-87 CHECKED R.M.H. 12/97 F-5.03 CADD NO. K.A.G. 08/03

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.